

GENERAL DEMOLITION KEYNOTES:

- A. SUB-CONTRACTORS ARE RESPONSIBLE FOR VERIFYING ALL EXISTING CONDITIONS IN THE FIELD. CONTRACTOR TO IMMEDIATELY REPORT ALL DISCREPANCIES TO THE ARCHITECT FOR CLARIFICATION
- B. PROTECT ALL STRUCTURES, FINISHES, ETC AND ADJACENT MATERIALS NOT INDICATED OR SCHEDULED FOR REMOVAL.
- C. EXISTING ELECTRICAL SERVICE TO BE CUT AND MADE SAFE BY ELECTRICAL SUBCONTRACTOR AND REMOVED BY DEMOLITION SUBCONTRACTOR.
- D. EXISTING MECHANICAL SERVICES TO BE CUT AND MADE SAFE BY MECHANICAL SUBCONTRACTOR AND REMOVED BY DEMOLITION SUBCONTRACTOR
- E. EXISTING PLUMBING SERVICE TO BE CUT AND MADE SAFE BY PLUMBING SUBCONTRACTOR AND REMOVED BY DEMOLITION CONTRACTOR.
- F. ALL EXPOSED EXTERIOR WIRING TO BE REWORKED TO INTERIOR.
- G. EXISTING STAINGLASS WINDOWS TO BE REMOVED AND SALVAGED FOR REUSE.



DEMOLITION KEYNOTES:

- 1. REMOVE EXISTING MASONRY FLUE, CHIMNEY, ETC.. TO BELOW ROOF LINE
- 2. REMOVE WINDOW, FRAME AND ALL ACCESSORIES
- 3. REMOVE PIERS / FOOTING
- 4. REMOVE ROOF STRUCTURE / MEMBRANE & EXTERIOR FINISHES
- 5. REMOVE DOOR, FRAME, AND ALL ACCESSORIES
- 6. REMOVE LADDER & RAILINGS
- 7. DEMOLISH EXISTING BUMPOUT
- 8. REMOVE EXISTING ROOFING
- 9. REMOVE EXISTING SIDING, TRIM, ETC..
- 10. REMOVE BULKHEAD / STAIRS
- 11. REMOVE EXISTING VENTS
- 12. REMOVE STEEL COLUMNS

PRICING SET

1	01/25/10	GENERAL REVISIONS
NO.	DATE	DESCRIPTION

SHEET TITLE:

**DEMOLITION
FRONT ELEVATION**

Job No.:	09020
FILE:	
DRAWN:	
SCALE:	1/4" = 1'-0"
DATE:	01/04/2010

SHEET IDENTIFICATION:

A1.02